

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac  
(County)

Located In:

Corner Code ##

- |                                    |                           |                    |
|------------------------------------|---------------------------|--------------------|
| 1. Public Land Survey              | T <u>11N</u> R <u>13E</u> | <u>B-13, C-113</u> |
|                                    | T _____ R _____           | _____              |
|                                    | T _____ R _____           | _____              |
|                                    | T _____ R _____           | _____              |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____              |
|                                    | S _____ T _____ R _____   | _____              |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____              |
|                                    | S _____ T _____ R _____   | _____              |

LIBER 1 PAGE 393  
RECEIVED FOR RECORD

93 DEC 14 PM 3:00

LIBER NO. 1 PAGE NO. 393  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Millettics, in a field survey on Aug 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- B - 13 Found P.K. nail in blacktop equal distance from SW Cor and SE Cor of Section
- C - 13 Found P.K. nail in blacktop used survey Recorded by Bert Walker Sept. 1993 to verify location.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- |                                |                             |
|--------------------------------|-----------------------------|
| B - 13                         | C - 13                      |
| S 1/4 Cor Section 31 T11N-R13E | SE Cor Section 31 T11N-R13E |
| Found P.K. nail                | Found P.K. nail             |

SURVEY &  
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |   |
|---|---|
| B - 13  | C - 13  |
| S 1/4 Cor Section 31 T11N-R13E                | SE Cor Section 31 T11N-R13E                   |
| Set Monu Box                                  | Set Monu Box                                  |
| East 3.53' to the N 1/4 Cor Sec. 5 (Monu Box) | West 4.33' to the NW Cor Section 4 (Monu Box) |
| S10°E 43.90' to a nail in a 30" Spruce        | N10°W 66.65' to a nail in a Power Pole        |
| N45°E 65.55' to a nail in a Power Pole        | N10°E 65.05' to a nail in a Power Pole        |
| N45°W 61.40' to a nail in a Tele Pole         | S45°E 26.90' to the SW cor of a Headwall      |

Signed by John A Millettics  
Surveyor's Michigan License No. 25859

Date Dec 13, 1993