

REMONUMENTATION CORNER

LIBER 1 PAGE 410  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 11N R 13E	F - 13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	Seg. 1
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
93 DEC 17 PM 1:56  
LIBER NO. 1 PAGE NO. 410  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on Dec 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
F - 13 Found no evidence of original corner in existence

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
F - 13  
S 1/4 Cor Section 33 T11N-R13E  
Set Corner using a proportional distance measured from the SE of 34 to the SW of 33 and a survey done April 1904 bt Bert Walker

SURVEY &  
REMONUMENTATION  
1993  
COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
F - 13  
S 1/4 Cor Section 33 T11N-R13E  
Set Monu Box  
N10°W 32.30' to the North end of a 36" CMP  
S10°W 31.90' to the South end of a 36" CMP  
East 2653.50' to the SE Cor Section 33 (Monu Box)

Signed by John A. Milletics Date Dec. 15, 1993  
Surveyor's Michigan License No. 25859