

REMONUMENTATION CORNER

LIBER

1 PAGE 408

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac Located In: Corner Code #
 (County)

1. Public Land Survey T 11N R 13E H - 13, G - 13
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

RECEIVED FOR RECORD
 93 DEC 17 PM 1:55
 LIBER NO. 1 PAGE NO. 408
 ESTHER LEE
 REGISTER OF DEEDS
 SANILAC CO., MICHIGAN
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Millettica, in a field survey on Aug 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H - 13 Found no evidence of original corner in existence

G - 13 Found no evidence of original corner in existence

SURVEY &
 REMONUMENTATION

1993

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H - 13

S 1/4 Cor Section 34 T11N-R13E

Set corner using a proportional distance measured from the SE of 34 to the SW of 33 and a survey done April 1904 by Bert Walker.

G - 13

SW Cor Section 34 T11N-R13E

Set corner using a proportional distance measured from the SE of 34 to the SW of 33 and a survey done April 1904 by Bert Walker.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H - 13

S 1/4 Cor Section 34 T11N-R13E

Set Monu Box

North 30.45' to a nail in a Railroad Tie
 N10°W 24.40' to the East end of a 12" CMP
 N40°W 40.06' to the West end of a 12" CMP
 East 2646.00' to the SE Cor Sec. 34

G - 13

SW Cor Section 34 T11N-R13E

Set Moun Box

N05°W 51.50' to the East end of a 12" CMP
 West 38.92' to the NW Cor Section 2 (Monu Box)
 S45°W 51.50' to a Stop Sign
 South 76.61' to a Bell Box
 East 2646.00' to the S 1/4 Cor Section 34

Signed by

John A Millettica

Date

Dec 16, 1993

Surveyor's Michigan License No.

25859