

REMONUMENTATION CORNER

LIBER 1 PAGE 407
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac (County) Located In: Corner Code #/

1. Public Land Survey T 11N R 13E J-13 L - 13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

RECEIVED FOR RECORD

93 DEC 17 PM 1:55

LIBER NO. 1 PAGE NO. 407
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics in a field survey on Aug 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J - 13 Found 1/2" iron in blacktop, per survey recorded in Liber 4, Page 581 of the Sanilac County Records.

L - 13 Found no evidence of original corner in existence

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J - 13	L - 13
S 1/4 Cor Section 35	S 1/4 Cor Section 36 T11N-R13E
Found 1/2 " iron bar	Set Monu box equal distance from the SE cor and the SW Cor of the Section and deeds from old church and school property.

SURVEY & REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J - 13	L - 13
S 1/4 Cor Section 35	S 1/4 Cor Section 36 T11N-R13E
Set Monu Box	Set Monu Box
N45°W 47.50' to a nail in a Power Pole	N30°W 50.82' to the SE Cor of a Church
S45°W 79.00' to a Stop Sign	N50°E 108.98' to the SW Cor of a School
East 2660.00' to the SE Cor of Section 35(Monu Box)	N05°E 118.30' to a nail in a 36" Maple

Signed by

John A Milletics

Date Dec. 15, 1993

Surveyor's Michigan License No. 25859