

JAN 19 2000

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:02

LIBER NO. 2 PAGE NO. 319  
MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

SECTION

For corners in

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T 11N R 14E	A-1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-1 Birch 20 N1E 41; Double Lynn 24 S22W 12; B. Ash 29 S43W 35; Hemlock 12 N36W 39; Elm 9 S14E 10; Sugar 11 N50E 52  
L.C.R.C. - None  
Unrecorded Surveys - I.E. Choep March 1972 - Kay Eng. Dec. 1973  
John Milletics Dec 1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1  
NW Corner Section 6, T11N-R14E  
Found 1/2" Iron in Monu Box per State Highway Book Page 65  
South 2771.25 to W 1/4 Corner  
Accepted as best evidence

APPROVED PEER BOARD MEETING  
NOV 19, 1999

*gm*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1  
NW Corner Section 1 T11N-R14E  
1/2 Iron in Monu Box  
North 10.5 feet to the Centerline M- 46  
N30°E 95.60 feet to a Nail East Side of Power Pole  
S45°E 47.75 feet to a Nail NE Side of Power Pole  
S60°W 101.70 feet to a Nail NW Side of Tele Pole

Signed by John A. Milletics  
Surveyor's Michigan License No. 25859

Date Oct 24, 1999

