

JAN 19 2000

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:02

LIBER NO. 2 PAGE NO. 320

MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T 11 N R 14 E	A-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	10			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-2 Lynn 28 S12W 43; Birch 8 N29W 18
Old Survey Liber - None
L.C.R.C. - None
Unrecorded Surveys - I.E. Chope March 1977 - Kay Eng Dec 1973
John Milletics Dec 1990 & Feb 1998
Act 132 - Liber 2 Page 345, Liber 2 Page 351-352, Liber 2 Page 363-364

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2
W 1/4 Corner Section 6, T11N-R14E
Found 1/2 Iron Bar in Gravel Road Bed
North 2771.25 feet to NW Corner
South 2662.90 feet to SW Corner

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 2
W 1/4 Corner Section 6, T11N-R14E
Monu Box with 1/2" Iron with cap
S40°W 100.10 feet to a nail in a Power Pole
East 28.75 feet to a nail in a Power Pole
N60°E 113.48 feet to the SW Corner of a House
North 2771.25 feet to the NW Corner of Section
South 2662.90 feet to the SW Corner of Section

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date Oct 24, 1999