

JAN 19 2000

LIBER

2 PAGE 321

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:02

LIBER NO. 2 PAGE NO. 321
MICHELE VAHORNAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC

(County)

Located In:

Corner Code #

1. Public Land Survey

T 11N R 14E

A-3

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3 Hemlock 12 N51W 18; DO 14 S52W 36
Old Survey Liber - None
Act 132 - Liber 4 Page 78
Unrecorded Survey Milletics Feb 1998, - Feb 1999
L.C.R.C. - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3
SW Corner Section 6, T11N-R14E
Found 1/2" Iron in gravel Road Bed
North 2662.90 feet to W. 1/4 Corner
South 2654.26 feet to W. 1/4 Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

gm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 3
SW Corner Section 1 T11N-R14E
1/2" Iron Bar in Gravel Road Bed
North 2662.90 feet to W 1/4 Corner
South 2654.26 feet to W 1/4 Corner
N45°W 75.00 feet to a Nail in a Power Pole
S60°W 60.95 feet to a Nail in a Power Pole
N45°E 49.25 feet to a Stop Sign
S45°E 44.80 feet to the NW Corner of a Bell Riser Box

Signed by *John A. Milletics*

Date 10-24-1999

Surveyor's Michigan License No. 25859

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													