

JAN 19 2000

LIBER

2 PAGE 322

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:02

For corners in

LIBER NO. 2 PAGE NO. 322  
NICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11</u> N R <u>14</u> E	A-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	10			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

A-4 Sugar 9 N10W 29; Birch 13 S22 1/2W 18 1/2  
Old Survey Liber - None  
Act 132 - Liber 4 Page 78  
Unrecorded survey - Dated Nov 1998  
L.C.R.C. - None


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4 W 1/4 Corner Section 7, T11N-R14E  
Found 5/8" Iron Bar in gravel Road Bed  
North 2654.26 to NW Corner  
South 2653.10 to SW Corner  
Accepted as best evidence

APPROVED PEER BOARD MEETING  
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 4  
W 1/4 Corner Section 7 T11N-R14E  
5/8" Iron Bar in gravel road Bed  
North 2654.26 feet to the NW Corner  
South 2653.10 feet to the SW Corner  
N45°E 39.10 to a Stop Sign  
West 58.00 feet to a nail in a Power Pole  
N85°W 15.40 to the North leg of a road sign



Signed by John A. Milletics

Date 10-24-99

Surveyor's Michigan License No. 25859