

JAN 19 2000

LIBER 2 PAGE 323

RECEIVED FOR RECORD

99 NOV 30 AM 9:02

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 323
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC
(County)

Located In:

Corner Code #

1. Public Land Survey

T 11 NR 14 E	A-5
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-5 Birch 15 N60W 37 1/2; DO 15 S5 1/2W 25
Old Survey Liber - None
L.C.R.C. - None
Act 132 - None
Unrecorded Survey Dated Nov 1998
Marshall Subdivision Recorded Liber 4 Page 29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5
SW Corner Seciton 7, T11N-R14E
Found 1/2 Iron Bar- Raised with 1/2" Iron bar
North 2653.10 feet to the W 1/4 Corner
South 2652.54 feet to the W 1/4 Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5
SW Corner Section 7 T11N-R14E
1/2" Iron Bar in gravel Road Bed
North 2653.10 feet to the W 1/4 Corner
South 2652.54 feet to the W 1/4 Corner
S45°W 33.90 feet to a stop sign
N45°W 82.10 feet to a nail in a Power Pole
N30°E 47.65 feet to a nail in a Power Pole
N45°E 38.90 feet to a stop sign



Signed by [Signature]
Surveyor's Michigan License No. 25859

Date Oct 24, 1999