

JAN 19 2000

LIBER

2 PAGE 325

RECEIVED FOR RECORD

99 NOV 30 AM 9:03

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 325
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>11</u> N R <u>14</u> E	<u>A-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-7 Hemlock 14 S3W 18; DO 12 N58 1/2W 35
Old Survey Liber - None
L.C.R.C. - None
Act 132 - Liber 2 Page 339 - Liber 3 Page 570

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7
SW Corner Section 18, T11N-R14E
Found 1/2" Iron Bar in gravel road bed
North 2665.46 feet to the W 1/4 Cor.
South 2656.65 feet to the W 1/4 Cor
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

gm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 7
SW Corner Section 18, T11N-R14E
1/2" Iron Bar in gravel road bed
N30°W 36.40 feet to a stop sign
N45°E 69.05 feet to a nail in a Power Pole
S30°E 36.20 feet to a stop sign
S45°W 32.80 feet to a stop sign
S30°W 65.00 feet to the NE Corner of Building
North 2665.46 feet to the W 1/4 Corner
South 2656.65 feet to the W 1/4 Corner

Signed by *John A. Milletics*
Surveyor's Michigan License No. 25859

Date 10-24-1999

