

JAN 19 2000

LIBER 2 PAGE 329

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 NOV 30 AM 9:03

For corners in

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T11N R 14 E	A-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER NO. 2 PAGE NO. 329
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Millettics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-12 Birch 12 N9W 26 1/2; Hemlock 12 S23W 30
Old Survey Liber - None
L.C.R.C. - None
Road Comm. - None
Act 132 - None
Unrecorded survey dated Aug 1987

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12
W 1/4 Corner Section 31 T11N-R14E
Found 1/2" Iron in gravel road bed
North 2653.78 feet to the NW Corner Section 31
South 2653.78 feet to the SW Corner Section 31
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 12
W 1/4 Corner Section 31 T11N-R14E
1/2" Iron Bar in Gravel Road Bed
North 2653.78 feet to the NW Corner Section 31
South 2653.78 feet to the SW Corner Section 31
N45°E 56.65 feet to a stop sign
S45°W 75.80 feet to a nail in a Power Pole
West 39.00 feet to a nail in a Fence Post
N60°W 62.22 feet to a nail in a Power Pole

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date Nov 3, 1999

