

SURVEY & REMONUMENTATION

APR 14 1998

SECTION REMONUMENTATION

LIBER 2 PAGE 162

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 DEC -2 AM 9:09

LIBER NO. 2 PAGE NO. 162
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

SURVEY & REMONUMENTATION

JAN 08 1998

Register of Deeds Section & File Number

For corners in WATERTOWN TOWNSHIP

Sanilac
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>11</u> N <u>R</u> <u>14</u> E	B - 9
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on July 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B - 9

GLO Notes

- Set 1/4 Section Post
- W. Ash 30 N30°E 26
- B. Ash 22 S24°W 13

Old Survey Liber survey dated April 1921 by Lotan Reed
Act 132 None
Act 74 None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B - 9

Found no evidence of corner at site, large drainage ditch to the north and south.

Set Box at a proportioned distance between the SE and SW Corners of the Section.

APPROVED PEER BOARD MEETING
NOV. 26, 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B - 9

- S 1/4 Corner Section 19, T11N-R14E Watertown Twp.
- Monu Box in place with 1/2" iron and cap
- S20°E 37.10 feet to the top centerline of a 48" CMP
- N20°E 34.10 feet to the top centerline of a 48" CMP
- N50°W 40.00 feet to a 1/2" Iron Bar
- S50°W 40.00 feet to a 1/2" Iron Bar
- West 2574.25 feet to the SW Cor Section 19
- East 2652.49 feet to the SE Cor Section 19



Signed by [Signature]
Surveyor's Michigan License No. 25859

Date Nov 12, 1997