

REMONUMENTATION CORNER

LIBER

1 PAGE 409

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|-------------|------------------|
| <u>Sanilac</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 11N R 14E | B - 13 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | <i>Seg. 1 pm</i> |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECEIVED FOR RECORD
 93 DEC 17 PM 1:56
 LIBER NO. 1 PAGE NO. 409
 ESTHER LEE
 REGISTER OF DEEDS
 SANILAC CO., MICHIGAN
 Register of Deeds Stamp & File Number

I, John A. Milletics, in a field survey on Aug 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 B - 13 Found no evidence of original corner in existence

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 B - 13
 S 1/4 Cor Section 31 T11N-R14E
 Set Corner at a equal distance from the SE Cor and the SW Cor of the Section(2645.08')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 B - 13
 S 1/4 Cor Section 31 T11N-R14E
 Set Monu Box
 N05°W 36.40' to a nail in a Fence Post
 N50°E 45.75' to a nail in a Fence Post
 N50°W 63.90' to a nail in a Fence Post
 East 2645.08' to the SE Cor Section 31

| | A | B | C | D | E | F | G | H | I | J | K | L | N |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

SURVEY &
 REMONUMENTATION
 1993
 COMMISSION

Signed by *John A. Milletics* Date Dec. 15, 1993
 Surveyor's Michigan License No. 25859