

REMONUMENTATION CORNER

LIBER 1 PAGE 404

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 16 PM 2:04

LIBER NO. 1 PAGE NO. 404  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO. MICHIGAN

For corners in

Sanilac (County) Located In: Corner Code #

1. Public Land Survey T 11N R 14E E - 13, D - 13  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, John A. Milletics, in a field survey on Aug 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E - 13 Found Monu Box in centerline of M-19 and the Marlette Road, per State Highway R/W Book and survey dated June 1982

D - 13 Found Rail Road Spike 6.90 south of blacktop centerline, as per survey dated June 1985 and consistent with Sanilac County Road Comm records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E - 13  
SE Cor Section 32 T11N-R14E  
Found Monu Box

D - 13  
S 1/4 Cor Section 32 T11N-R14E  
Found Railroad Spike

SURVEY &  
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 13  
SE Cor Section 32 T11N-R14E  
Found Monu Box  
S80°W 54.25' to a concrete right of way marker  
N45°W 67.85' to a nail in a Power Pole  
S80°E 61.60' to a concrete right of way marker

D - 13  
S 1/4 Cor Section 32 T11N-R14E  
Found Rail road spike  
Set Monu Box  
North 49.85' to a nail in a 24" ash  
N30°E 47.20' to the east end of a 12" CMP  
East 2652.00' to the SE Cor of said Section

Signed by John A. Milletics

Date Dec 15, 1993

Surveyor's Michigan License No. 25859