

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac (County) Located In: Corner Code #
1. Public Land Survey T 11N R 14E H - 13, J - 13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

RECEIVED FOR RECORD

93 DEC 29 AM 10:53

LIBER NO. 1 PAGE NO. 422
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Dec 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Numbers 1-36 are placed in the grid cells.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H - 13
Found no evidence of original corner in existence

J - 13
Found no evidence of original corner is existence

SURVEY &
REMONUMENTATION
1993
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H - 13
S 1/4 Cor Section 34 T11N-R14E
Set set corner using a proportional measurement between the existing fences

J - 13
S 1/4 Cor Section 35 T11N-R14E
Set Cor at a equal distance between the SE cor Section 35 and the SW cor Section 35

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H - 13
S 1/4 Cor Section 34 T11N-R14E
Set Monu Box
N60°E 108.45' to a nail in a Power Pole
N70°W 192.90' to a nail in a Power Pole
S70°W 136.65' to the East end of a 12" CMP
East 2657.74' to the SE Cor Section 34

J - 13
S 1/4 Cor Section 35 T11N-R14E
Set Monu Box
N05°E 40.20' to a nail in a Fence Post
S20°W 25.90' to the South end of a 24" CMP
S45°E 68.90' to a nail in a Power Pole
East 2656.00' to the SE Cor Section 35
West 2656.00' to the SW Cor Section 35

Signed by [Signature] Date Dec 24, 1993
Surveyor's Michigan License No. 25859