

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac (County) Located In: Corner Code ##

1. Public Land Survey T 11N R 14E L - 13 K - 13

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

RECEIVED FOR RECORD

93 DEC 29 AM 10:55

LIBER NO. 1 PAGE NO. 431  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A Milletics, in a field survey on Nov 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L - 13 Found Monu Box in centerline of paved surface, per survey dated 8-31-81
- K - 13 Found Monu Box in centerline of paved surface, per survey dated 4-27-1977

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L - 13 S 1/4 Cor Section 36 T11N-R14E Found Monu Box
- K - 13 SW Cor Section 36 T11N-R14E Found Moun Box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L -13 S 1/4 Cor Section 36 T11N-R14E Monu Box  
N05°E 31.15' to the North end of a 24" CMP  
S05°E 30.00' to the South end of a 24" CMP  
N70°E 196.22' to a nail in a Power Pole
- K -13 SW Cor Section 36 T11N-R14E Monu Box  
N45°E 75.50' to a nail in a Power Pole  
S05°W 18.75' to the East leg of a Road Sign  
N45°W 44.20' to the West end of a 24" CMP

SURVEY & REMONUMENTATION

1993

COMMISSION

Signed by John A Milletics Date Dec. 24, 1993  
Surveyor's Michigan License No. 25859