

NOV 21 1997

LIBER

2 PAGE 142

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 SEP -9 AM 8:58

LIBER NO. 2 PAGE NO. 142

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T11NR 14E	D -13
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on June 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- D -13
- GLO NOTES
- White Ash 7 N54°W 1½
- Hemlock 8 N52°E 21½

APPROVED PEER BOARD MEETING
Aug 18, 1997 JM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D -13
- Found Moun Box in place - removed by the Sanilac County Road Comm during reconstruction of road - REPLACED using Act 74 as recorded in Liber 1 Page 404

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D - 13
- S 1/4 Corner Section 32 T11N-R14E
- MONU BOX with iron and cap
- North 49.85 feet to a nail in a 24" Ash
- N10°E 52.60 feet to a nail in a 12" Ash
- S50°E 93.38 feet to a nail in a Fence Post
- East 2652.00 feet to the SE Cor of Sec. 32



Signed by [Signature]
Surveyor's Michigan License No. 25859

Date Aug 11, 1997