

SURVEY  
REMONUMENTATION

1993

LIBER

1 PAGE 433

REMONUMENTATION  
COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac  
(County)

Located in:

Corner Code ##

- |                                       |                           |                       |
|---------------------------------------|---------------------------|-----------------------|
| 1. Public Land Survey                 | T <u>11N</u> R <u>15E</u> | <u>J - 13, I - 13</u> |
|                                       | T _____ R _____           | _____                 |
|                                       | T _____ R _____           | _____                 |
|                                       | T _____ R _____           | _____                 |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____                 |
|                                       | S _____ T _____ R _____   | _____                 |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____                 |
|                                       | S _____ T _____ R _____   | _____                 |
| 4. Lot No. _____, Recorded Plat _____ |                           |                       |
| 5. Private Claims _____               |                           |                       |

RECEIVED FOR RECORD

93 DEC 29 AM 10:55

LICENS. NO. \_\_\_\_\_  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A. Millette in a field survey on Oct 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M  |
|----|----|---|----|---|----|---|----|---|----|---|----|---|----|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   |    |   |    |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |    |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |    |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |    |
| 6  | 16 |   | 17 |   | 18 |   | 19 |   | 20 |   | 21 |   | 22 |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |    |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |    |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |    |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |    |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |    |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |    |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |    |

- A. Description of original monument and accessories and/or subsequent restoration:
- J - 13  
Found 1/2" iron bar in gravel road bed, per survey dated 10-6-85
  - I - 13  
Found 1/2" iron bar in gravel road bed, per survey dated 7-13-84

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- |   |  |
|---|--|
| J - 13<br>S 1/4 Cor Section 35 T11N-R15E<br>Found 1/2" iron bar | I - 13<br>SW Cor Section 35 T11N-R15E<br>Found 1/2" Iron Bar |
|---|--|

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |   |  |
|---|--|
| J - 13<br>S 1/4 Cor Section 35 T11N-R15E<br>1/2" iron bar<br>N70°E 94.65' to a nail in a 18" Ash<br>N50°E 47.35' to a nail in a Tele Pole<br>South 21.20' to the West leg of a Road Sign<br>N30°W 37.70' to a Stop Sign | I - 13<br>SW Cor Section 35 T11N-R15E<br>1/2" iron bar<br>N45°W 67.25' to a nail in a 24" Ash<br>N55°E 52.55' to a nail in a Fence Post<br>S45°E 32.70' to a nail in a Power Pole<br>S10°W 27.00' to a nail in a 10" Ash |
|---|--|

Signed by John A. Millette Date Dec. 24, 1993  
Surveyor's Michigan License No. 25859