

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Sanilac</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>15E</u>	<u>K - 13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD

93 DEC 29 PM 1:44

LIBER NO. 1 PAGE NO. 442  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Dec 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K - 13  
Found 1" pipe in low swamp area, per survey dated 7-23-85

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K - 13  
SW Cor Section 36 T11N-R15E  
Found 1" Pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K - 13  
SW Cor Section 36 T11N-R15E  
1" iron pipe  
North 7.08' to a nail in a 12" Twin Cottonwood  
N80°W 28.4' to a nail in a 10" Ash  
N80°E 28.9' to a nail in a 20" Ash  
South 84.0' to a nail in a 36" Oak

Signed by John A Milletics Date Dec 29, 1993  
Surveyor's Michigan License No. 25859