JAN 2 2 2001

3 BAGE 66 LIBER

RECEIVED FOR RECORD

SECTION

2000 REMONUMENTATION PROGRAM AND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 LIBER NO. PAGE NO. HICHELE VANNORMANI REGISTER OF DEEDS LAND CORNER RECORDATION CERTIFICATE

00 DEC -1 AM 9:33

SAHILAC CO. HICHGAN

For corners in		- ,
Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T11N R TR TR TR	15E G - 1
Property Controlling in Section	S TR S TR	
Miscellaneous     Property in Sec.	S TR S TR	

Register of Deeds Stamp & File Number

4. Lot No ,	Recorded Plat	
5. Private Claims	•	

2000

I, John A M1.11etics \_\_, in a field survey on May 1 \_\_, 183x \_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in , 199X conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	В	С	D	E	F	G 1	H	1	J 1	K :	LA
1	Γ	П	T	Т	Т	T	7	T	Г			1
2		6	+	· 5	+	ģ —	╁	<u> </u>	-	ģ	-	į
3	$\vdash$	1-	╂	+	+-	╫	$\vdash$	╀	<u> </u>	-	<del> </del>	<u> </u>
4	-	ļ 7	-	8	+-	9	<del> </del> 1	  0		1	-1	2
5	<del> </del>	$\vdash$	╀	╬	╁	-	├		├		<del> </del> —	<u> </u>
6	<u> </u>	! ! <del>0</del>	lacksquare	1,7-	$\perp$	16—	<u> </u> _1	5—	ļ_,	4	11	3_
7	L.	↓_	<del> </del> _	╀-	$\bot$	↓_	_	<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>
8		9_	-	20-	1	21_	<u> </u> 2	22_	<u> </u> -2	3	2	4
9		<u> </u>	1	<u> </u>	1_	<del> </del>		<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>
10	_	30	-	 29_	-	28	-2	] 27	-2	6	<u> </u> -2	[ 5—
11	_	<u> </u>	╀	十	lacksquare	┞	┞	┡	<u> </u>		<u> </u>	ļ
12	L,	 31	<u>L</u>	 32		33	L	 		  5	L	l 16—
		1		1		1		1		Ī	~	Ĭ
13		ــــــــــــــــــــــــــــــــــــ		_				<u>.                                      </u>		<b>!</b>	J	

A. Description of original monument and accessories and/or subsequent restoration:

NW Corner Section 3 TllN-R15E

GLO Notes

Elm 12" N71°W 36 Links

6" S72½E 31 Links Ash

Act 132 - None L.C.R.C. Forms - None

Unrecorded surveys - Kay Engineering Jan 1973- Milletics Dec 1989-Sanilac Land Survey Nov 1980 - Milletics Jan 2000

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NW Corner Section 3 TllN-R15E

Found P.K. Nail in place in blacktop surface

West 2647.10 feet to the N 1/4 Corner Section 4

East 2624.05 feet to the N 1/4 Corner Section 3

Accepted as best evidence



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 1

NW Corner Section 3 TllN-R15E

1/2" Iron Bar with cap in concrete

East 5.84 feet to the SW Corner Section 34

South 29.35 feet to the present centerline M- 46

N60°W 13.64 feet to a stop sign

N20°W 85.85 feet to a nail in a Telephone Pole

N45°E 89.00 feet to a nail in a Telephone Pole

N60°E 58.78 feet to a nail in a Anchor Pole

West 2647.10 feet to the N 1/4 Cor Sec. 4 - East 2624.05 feet to the N 1/4 Cor Sec 3

Signed by On A Milletus	Date	Nov 15, 2000	
Surveyor's Michigan License No. 25859			

APPROVED PEER BOARD

MEETING NOV 25 2000