

JAN 19 2000

LIBER

2 PAGE 357

RECEIVED FOR RECORD

99 NOV 30 AM 9:04

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 357
MICHELE VANHORN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T 11N R 16 E	A-1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-1 Birch 10 N16 1/2E 8 1/2; Elm 24 S57 1/2W 16; Birch 10 N16 1/2E 8 1/2; DO 9 N76E 24; DO 14 S38E 34; DO 12 N70 1/2W 47 1/2
Old Survey Liber
L.C.R.C. - None
Act 132 - None
Unrecorded survey - Milletics Dated May 1994 - Kay Eng Dated April 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1
NW Corner Section 6, T11N-R16E
Found no evidence of corner State Highway Department rebuild M-46 and removed all evidence of corner
North 2657.22 feet to the W 1/4 Corner Section 31 T12N-R16E
South 2650.40 feet to the W 1/4 Corner Section 6 T11N-R16E
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 1
NW Corner Section 6 T11N-R16E
Monu Box with 1/2" Iron Bar with cap
North 2657.22 feet to the W 1/4 Corner Section 31 T12N-R16E
South 2650.40 feet to the W 1/4 Corner Section 6 T11N-R16E
N45°E 59.90 feet to a nail in a Light Pole
N45°W 102.60 feet to a nail in a Power Pole
N30°W 56.90 feet to the East leg of a Stop Sign
S45°E 63.80 feet to the NW Corner of a Bell Riser Box
S70°E 80.60 feet to a Road Sign

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date 11-15-1999