

JAN 19 2000

LIBER

2 PAGE 360

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:04

SECTION

For corners in

LIBER NO. 2 PAGE NO. 360
MICHELE VANHORNAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T 11 N R 16 E	A-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-4 Hemlock 36 N71W 20; DO 13 S32W 26
Old Survey Liber - None
L.C.R.C. - None
Act 132 - Liber 2 Page 497 shows section line straight thru
Unrecorded survey - None found

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4
W 1/4 Corner Section 7, T11N-R16E
Set 1/2" iron bar at a equal distance between the NW & SW corner on a straight line. Iron did match occupation to east
North 2649.00 feet to NW Corner
South 2649.00 feet to SW Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 4
W 1/4 Corner Section 7 T11N-R16E
1/2" iron bar in gravel road bed with cap
North 2649.00 feet to the NW Corner
South 2649.00 feet to the SW Corner
N45°E 30.65 feet to a nail in a 9" Apple
N30°E 55.60 feet to a nail in a 6" Apple
S75°E 23.26 feet to a nail in a 6" Apple

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date 11-15-1999