

JAN 19 2000

LIBER 2 PAGE 361

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:04

LIBER NO. 2 PAGE NO. 361
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 11 N R 16 E A-5
- T R _____
- T R _____
- T R _____
- 2. Property Controlling S T R _____
- in Section S T R _____
- 3. Miscellaneous S T R _____
- Property in Sec. S T R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-5 Pine 28 S60W 39; Sugar 16 N17 1/2W 38 1/2
Old Survey Liber - None
L.C.R.C. - None
Act 132 - Liber 2 Page 497
Unrecorded survey - Milletics Dated May 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5
SW Corner Section 7, T11N-R16E
Found 1/2" Iron bar in Monu. Box
North 2649.00 feet to the W 1/4 Corner Section 7
South 2647.40 feet to the W 1/4 Corner Section 18
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

gm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 5
SW Corner Section 7 T11N-R16E
1/2" Iron bar with cap in Monu. Box
North 2649.00 feet to the W 1/4 Corner Section 7
South 2647.40 feet to the W 1/4 Corner Section 18
N30°W 70.00 feet to the SE Corner of a Bell Riseer Box
N25°W 44.00 feet to a Stop Sign
N45°E 48.00 feet to the East end of a 24" CMP
S45°E 46.51 feet to a Stop Sign

Signed by *John A. Milletics*
Surveyor's Michigan License No. 25859

Date 11-15-1999