

JAN 19 2000

LIBER 2 PAGE 362

RECEIVED FOR RECORD

99 NOV 30 AM 9:04

SECTION

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIBER NO. 2 PAGE NO. 362  
MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11</u> N R <u>16</u> E	<u>A-6</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-6 B. Ash 14 S37W 25; DO 12 N5W 7 1/2  
Old Survey Liber - None  
L.C.R.C. - None  
Act 132 - None  
Unrecorded survey - Milletics Dated May 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6  
W 1/4 Corner Section 18, T11N-R16E  
Found 1/2" Iron bar in gravel road bed  
North 2647.40 feet to the NW Corner Section 18  
South 2647.40 feet to the SW Corner Section 18  
Accepted as best evidence

APPROVED PEER BOARD MEETING  
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 6  
W 1/4 Corner Section 18 T11N-R16E  
1/2" Iron bar in gravel road bed  
North 2647.40 feet to the NW Corner Section 18  
South 2647.40 feet to the SW Corner Section 18  
S50°W 40.36 feet to a nail in a 48" Maple  
S80°W 33.70 feet to a nail in a 15" Ash  
N60°W 36.75 feet to a nail in a 30" Twin Ash  
N35°W 56.78 feet to a nail in a 24" Ash  
N45°E 49.80 feet to a nail in a Fence Post

Signed by John A. Milletics  
Surveyor's Michigan License No. 25859

Date 11-15-1999