

JAN 19 2000

LIBER 2 PAGE 363

RECEIVED FOR RECORD

99 NOV 30 AM 9:04

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIBER NO. 2 PAGE NO. 263
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

| | | |
|---------------------------------------|--------------|---------------|
| <u>SANILAC</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 11N R 16 E | A-7 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

A-7 Birch 10 N36W 60; DO 7 S46W 17 3/4
Old Survey Liber - None
Act 132 - None
Unrecorded Survey - Sanilac Land Dated Aug 1977 - Milletics Dated Aug 1987
Milletics Dated Dec. 1992

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7
SW Corner Section 18, T11N-R16E
Found 1" Iron Bar in Gravel Road Bed
North 2647.40 feet to the W 1/4 Corner Section 18
South 2654.43 feet to the W 1/4 Corner Section 19
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 7
SW Corner Section 18 T11N-R16E
1" Iron bar in gravel road bed
North 2647.40 feet to the W 1/4 Corner Section 18
South 2654.43 feet to the W 1/4 Corner Section 19
S45°W 37.61 feet to a Stop Sign
N45°W 49.38 feet to the SE Corner of a Bell Riser Box
N30°W 36.90 feet to a stop sign
N45°E 33.45 feet to a stop sign
S45°E 88.86 feet to a nail in a Power Pole
S30°E 38.20 feet to a stop sign

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date 11-15-1999