

JAN 19 2000

LIBER

2 PAGE 364

RECEIVED FOR RECORD

99 NOV 30 AM 9:04

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

LIBER NO. 2 PAGE NO. 364
NICHELE YANHORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T11NR 16E	A-8
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

A-8 Elm 7 N14W 11 1/2; DO 9 S6W 7 1/2
Old Survey Liber = None
L.C.R.C. - None
Act 132 - Liber 3 Page 752
Unrecorded Survey - Sanilac Land Dated July 1977, Sanilac Land Dated Aug 1977
Milletics Dated Sept 1990, Milletics Sept 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8
W 1/4 Corner Section 19, T11N-R16E
Found 1/2" Iron Bar in gravel road bed
North 2654.43 feet to the NW Corner Section 19
South 2648.17 feet to the SW Corner Section 19
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 8
W 1/4 Corner Section 19 T11N-R16E
1/2" Iron bar in gravel road bed with cap
North 2654.43 feet to the NW Corner Section 19
South 2648.17 feet to the SW Corner Section 19
N50°W 46.39 feet to a nail in a 18" Poplar
N30°W 73.15 feet to a nail in a 12" Ash
N80°E 71.75 feet to a nail in a Power Pole
East 33.00 feet to a 1/2" Iron bar

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date 11-15-1999