

JAN 19 2000

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:04

SECTION

For corners in

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T11N R 16 E	A-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER NO. 2 PAGE NO. 365
MICHELE VANHORNAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	10			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

A-9 Sugar 11 - 5 1/2; Birch 24 N33W 51
Old Survey Liber - None
Act 132 - Liber 3 Page 752
L.C.R.C. - None
Unrecorded survey - Sanilac Land Dated July 1977, Sanilac Land Dated Feb 1980
Milletics Sept 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9
SW Corner Section 19, T11N-R16E
Found 1" Iron Bar in gravel Road Bed
North 2648.17 feet to the W 1/4 Corner Section 19
South 2649.16 feet to the W 1/4 Corner Section 30
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 9
SW Corner Section 19 T11N-R16E
1" Iron bar in gravel road bed
North 2648.17 feet to the W 1/4 Corner Section 19
South 2649.16 feet to the W 1/4 Corner Section 30
N30°W 37.30 feet to a stop sign
S45°E 50.13 feet to a nail in a Power Pole
S30°W 64.58 feet to a nail in a 36" Poplar
S60°W 69.45 feet to a nail in a Tele Pole

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date 11-15-1999