

JAN 19 2000

LIBER 2 PAGE 366

SECTION

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE 99 NOV 30 AM 9:04
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T11N R 16 E	A-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER NO. 2 PAGE NO. 366
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-10 Birch 9 N52W 3 1/3; Hemlock 9 S35W 37
Old Survey Liber - None
Act 132 - None
L.C.R.C. - None
Unrecorded survey - Milletics Dated Aug 1987, Milletics Dated April 1991

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10
W 1/4 Corner Section 30, T11N-R16E
Found 1/2" iron bar in gravel road bed
North 2649.16 feet to the NW Corner Section 30
South 2644.26 feet to the SW Corner Section 30
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

gm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 10
W 1/4 Corner Section 30 T11N-R16E
1/2" Iron bar in gravel road bed with cap
North 2649.16 feet to the NW Corner Section 30
South 2644.26 feet to the SW Corner Section 30
S80°W 23.39 feet to the north leg of a road sign
N60°E 26.83 feet to a stop sign
S70°E 62.50 feet to a Road Sign
S40°E 65.55 feet to a nail in a 15" Pine

Signed by *John A. Milletics*
Surveyor's Michigan License No. 25859

Date 11-15-1999