

JAN 19 2000

LIBER 2 PAGE 367

RECEIVED FOR RECORD

99 NOV 30 AM 9:05

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 367
MICHELE VANORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 11N R 16 E A-11
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 - A-11 Maple 20 N48W 10 1/2; Birch 7 S57W 18; Birch 2 N44W 42
 - Old Survey Liber - None
 - L.C.R.C. - None
 - Act 132 - Liber 3 Page 299
 - Unrecorded survey - Milletics Dated April 1982, Milletics Dated Aug 1987
 - Milletics Dated May 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-11 SW Corner Section 30, T11N-R16E
- Found 1/2" Iron bar in Moun Box in pavement
- North 2644.26 feet to the W 1/4 Corner Section 30
- South 2645.76 feet to the W 1/4 Corner Section 31
- Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A - 11
- SW Corner Section 30 T11N-R16E
- 1/2" iron bar in monu box with cap
- North 2644.26 feet to the W 1/4 Corner Section 30
- South 2645.76 feet to the W 1/4 Corner Section 31
- N30°W 40.65 feet to a Stop Sign
- N45°E 44.57 feet to a nail in a Power Pole
- S30°E 63.70 feet to a nail in a Power Pole
- S45°W 47.94 feet to a nail in a Tele Pole

Signed by

Surveyor's Michigan License No. 25859

Date 11-15-1999