

JAN 19 2000

LIBER

2 PAGE 368

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 368
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11</u> N R <u>16</u> E	A-12
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-12 Birch 7 N68 1/2W 8 1/2; D0 10 S50 1/2W 30 1/2
Old Survey Liber - None
Act 132 - Liber 3 Page 745
L.C.R.C. - None
Unrecorded survey - Sanilac Land Dated July 1979, Milletics Dated April 1982
Milletics Dated May 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12
W 1/4 Corner Section 31, T11N-R16E
Found 1/2" Iron Bar in gravel road bed
North 2645.76 feet to the NW Corner Section 31
South 2646.62 feet to the SW Corner Section 31
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

gm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 12
W 1/4 Corner Section 31 T11N-R16E
1/2" Iron Bar in Gravel Road Bed
North 2645.76 feet to the NW Corner Section 31
South 2646.62 feet to the SW Corner Section 31
S85°E 60.20 feet to a nail in a Power Pole
West 64.05 feet to a nail in a Power Pole
S70°W 105.20 feet to the NE Corner of a Shed

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date 11-15-1999