

1993  
REMONUMENTATION  
COMMISSION

1993  
REMONUMENTATION  
COMMISSION

LIBER 1 PAGE 436

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Sanilac</u> <small>(County)</small>	Located In:	Corner Code =#
1. Public Land Survey	T 11N R 16E	D - 13, C - 13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD

93 DEC 29 AM 10:56

LIBER NO. 1 FILE NO. 436  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Oct 12, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

D - 13  
Found 1" Pipe in gravel road bed, per survey dated 10-15-90

C - 13  
Found 1/2" iron bar in gravel road bed, per survey recorded in Liber 4 Page 633 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D - 13	C - 13
S 1/4 Cor Section 32 T11N-R16E	SW Cor Section 32 T11N-R16E
Found 1" iron bar	Found 1/2" iron bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D - 13	C - 13
S 1/4 Cor Section 32 T11N-R16E	SW Cor Section 32 T11N-R16E
1" iron pipe	1/2" iron Bar
S15°W 26.50' to a nail in a 18" Maple	N45°W 53.45' to a nail in a Power Pole
S45°E 34.10' to a nail in a 24" Maple	S50°W 65.00' to a nail in a Power Pole
North 50.30' to a nail in a Power Pole	South 20.45' to the West Leg of a Road Sign
	East 216.38' to the N 1/4 Cor Section 4

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by John A Milletics Date Dec 24, 1993  
Surveyor's Michigan License No. 25859