

1993

LIBER

1 PAGE 437

REMONUMENTATION COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac (County) Located In: Corner Code ##

1. Public Land Survey T 11N R 16E F - 13 E - 13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD

93 DEC 29 AM 10:57

LIBER 1 PAGE NO. 437  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO. MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A Millerica, in a field survey on Oct 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F - 13

Found 5/8" iron bar in gravel road bed, per survey dated 6-19-87 and previous Collins survey

E - 13

Found 5/8" iron bar in gravel road bed, per survey dated 6-19-87 and previous Collins survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F - 13

S 1/4 Cor Section 33 T11N-R16E

Found 5/8" iron bar

E - 13

SW Cor Section 33 T11N-R16E

Found 5/8" iron bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F - 13

S 1/4 Cor Section 33 T11N-R16E

5/8" iron bar

N45°W 99.50' to a nail in a Power Pole

South 16.60' to the East Leg of a Road Sign

N45°E 65.77' to a nail in a Fence Post

N20°W 41.60' to a Stop Sign

E - 13

SW Cor Section 33 T11N-R16E

5/8" iron bar

East 239.33' to the N 1/4 Cor Section 3

N30°W 43.90' to a Stop Sign

South 20.90' to the West Leg of a Road Sign

N45°E 50.25' to a nail in a Fence Post

Signed by John A Millerica

Date Dec 24, 1993

Surveyor's Michigan License No. 25859