

1993

LIBER 1 PAGE 414

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 28 AM 10:39

COMMISSION

For corners in

LIBER 1 PAGE NO. 414
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T 11N R 16E	H -13, G - 13
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on Oct 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H - 13

Found 5/8" iron bar in gravel road bed, per survey recorded in Liber 2, Page 380 of the Sanilac County Records.

G - 13

Found 1/2" iron bar in gravel road bed, per survey recorded in Liber 3, Page 235 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H - 13

S 1/4 Cor Section 34 T11N-R16E

Found 5/8" iron bar

G - 13

SW Cor Section 34 T11N-R16E

Found 1/2" iron bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H - 13

S 1/4 Cor Section 24 T11N-R16E

5/8" iron bar

N40°E 51.35' to a nail in a Power Pole

N30°E 47.05' to a nail in a Power Pole

N70°W 54.50' to the east leg of a Road Sign

West 54.53' to the NW Cor Section 1

G - 13

SW Cor Section 34 T11N-R16E

1/2" iron bar

North 33.00' to a iron bar

S30°E 40.70' to a nail in a cor fence post

S10°W 77.15' to a nail in a 18" Apple

Signed by John A Milletics
Surveyor's Michigan License No. 25895

Date Dec. 24, 1993