

1993

LIBER

1 PAGE 415

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 28 AM 10:39

For corners in COMMISSION

LIBER NO. 1 PAGE NO. 415
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

| | | |
|---------------------------------------|-------------------------|----------------|
| Sanilac (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 11N R 16E | J - 13, I - 13 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | N |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, John A Milletics, in a field survey on Oct 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J - 13

Found 5/8" iron bar in gravel road bed, per Irvin E. Choape survey

I - 13

Found 1/2" iron bar in gravel road bed, per Burnside Subdivision as recorded in Liber 4, Page 23 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J - 13

S 1/4 Cor Section 35 T11N-R16E
Found 5/8" iron bar

I - 13

SW Cor Section 35 T11N-R16E
Found 1/2" iron bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J - 13

S 1/4 Cor Section 35 T11N-R16E
5/8" iron bar
S40°W 42.70' to the NW cor post of a clear vision fence
N40°E 46.95' to the SW cor post of a clear vision fence
East 157.60' to the NE Cor Section 1(monu box)

I - 13

SW Cor Section 35 T11N-R16E
1/2" iron bar
N45°E 40.45' to a nail in a 24"Willow
N30°E 28.20' to a steel post
N45°W 27.00' to the north end of a
18"CMP

Signed by John A Milletics Date Dec. 24, 1993
Surveyor's Michigan License No. 25859