

SURVEY & REMONUMENTATION

LIBER

2 PAGE 303

RECEIVED FOR RECORD

SEP 17 1999

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 AUG -2 AM 9:09

LIBER NO. 2 PAGE NO. 303
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in SECTION
SANILAC
(County)

Located In: Corner Code #

1. Public Land Survey	T 12N R 12E	A-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Millettics, in a field survey on April 1, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Township corner established- Hemlock 24 S64W 20; Hemlock 10 N23½E 5
- 1889 (Resurvey of Evergreen Twp., T13N-R12E, Sanilac County) F.F. Rogers, Surveyor-Set Vitrified Stone (corner) 3 inches in diameter and 3 feet in the Earth-gives no accessories, but says set from old stake planted by J.A. Teskey from bearing trees and checked by Rogers
- 1974 (Survey-Liber 3 of Surveys, pages 116&117, Sanilac County) Irvin E. Choep, P.S. 6504, Survey is of Section 31, T13N-R12E and shows Southwest corner of Section 31. Gives no object marking corner and no Accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 1
NW Corner Section 6 T12N-R12E
Found Standard Concrete Monument with Brass Cap
South 2759.40 feet to the W 1/4 Corner
North 2638.80 feet to the W 1/4 Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
July 20, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 1
Standard Concrete Monument with Brass Cap
N54°E, 51.41' T.C. Re-mon. tag in Northwest face of 14" Poplar (also nail & flagging S.W. face)
S68°E, 84.69' T.C. Re-mon. tag in Southwest face of 8" Basswood
S42°E, 41.05' T.C. Re-mon. tag in West leg of upright Steel Vehicle Frame
N75°W, 29.78' T.C. Re-mon. tag above found nail in South face of Telephone pedestal Support post

Signed by John A. Millettics
Surveyor's Michigan License No. 25859

Date June 30, 1999

