

SURVEY & REMONUMENTATION

SEP 17 1999

LIBER

2 PAGE 305

RECEIVED FOR RECORD

99 AUG -2 AM 9:09

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 305
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

SECTION

For corners in

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T12N R12E	A-3
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on April 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Set post corner Secs. 1&12-Hemlock 12 N31W 8; Hemlock 9 South 9
 - 1919 (Tuscola County Road Commission witness card record) "Point of large Stone"-N55°45'E 59.0 Southeasterly* 36.7; Southwesterly* 40.5; N47°W 40.9---*direction as indicated @ sketch on card--no bearing objects given
 - 1973 (Survey-Liber 430, pages 459&660 Tuscola County) David T. Rowe, P.S. 11192-Set PK Nail N15°E, 59.70'-RLS tag 11192 in PP; N50°W, 71.71' RLS 11192 tag in 14" Maple; S40°W, 44.91 Road Sign Post
 - 1976 (Land Corner Recordation Certificate) David T. Rowe, P.S.11192-Re-set PK nail by using occuppies fence lines and center-line of Road--Accessories same as 1973 Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 3
SW Corner Section 6 T12N-R12E
Found Standard Concrete Monument with Brass Cap
North 2630.35 feet to the W 1/4 Corner Section 6
South 2628.25 feet to the W 1/4 Corner Section 7
Accpcted as best evidence

APPROVED PEER BOARD MEETING
July 20, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Standard Concrete Monument with 2" Brass Cap in Monument Box
N58°E, 64.64' T.C. Re-mon. tag in Southeast face of Power Pole
S42°E, 48.26' T.C. Re-mon. tag in Southwest face of Power Pole
S30°W, 68.47' T.C. Re-mon. tag above found nail in Northwest face of Telephone Pole Stub
S44°W, 45.0' Face of Road Name Sign Steel Post
N55°W, 71.56' T.C. R-cmon. tag above found nail in 24" Maple

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date June 30, 1999

