

SURVEY & REMONUMENTATION

SEP 17 1999

LIBER 2 PAGE 306

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

99 AUG -2 AM 9:09

SECTION

LIBER NO. 2 PAGE NO 306
 MICHELE VANNORMAN
 REGISTER OF DEEDS
 SANILAC CO., MICHIGAN

For corners in

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T12N R12E	A-4
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John A. Millettics, in a field survey on April 1, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Set qu. Sec. post- Elm 7 N55½W 6; Elm 7 S29W7 Tuscola County L.C.R.C. form Recorded Liber ___ Page ___ Filing No. 48

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 4
 W. 1/4 Corner Section 7 T12N-R12E
 Found Standard Concrete Monu. with Brass Cap
 North 2628.25 feet to the NW Corner Section 7
 South 2828.10 feet to the SW Corner Section 7
 Accepted as best evidence

APPROVED PEER BOARD MEETING
 July 20, 1999 *gm*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Standard Concrete Monument with 2" Brass Cap
 N30°E, 22.72' Set ½" diameter reinforcing rod
 S25°E, 21.88' Set ½" diameter reinforcing rod
 S30°W, 21.60' Set ½" diameter reinforcing rod
 N30°W, 21.83' set ½" diameter reinforcing rod



Signed by *John A. Millettics*
 Surveyor's Michigan License No. 25859

Date June 30, 1999