

SEP 17 1999

LIBER

2 PAGE 309

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE

99 AUG -2 AM 9:09

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 309

MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T12N R12E	A-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on April 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 (Gov't. Land Office Noted) Harvey Parke, D.S.-Set post corner Secs. 13&24-Hemlock 10 N8W 6; Hemlock 8 S25W 18
 - 1961 (Tuscola County Road Plan) James L. Scott, Professional Engineer-Plan shows "Approx. Sec. Cor." Sections 13, 24 T12N-R11E 18, 19 T12N-R12E-N45°W 37.38' P. Pole; N70°W 86.23' Well pipe S45°W 32.28' Cor. Fence Post
 - 1973 (Survey-Liber 432, page 226; Tuscola County) Robert G. Kay, P.S. 14096-Shows SE Cor, Sec 13 T12N-R11E (no object mentioned) N40°W 37.25' Nail in P.P.: S70°E 86.25' Steel sign Post; S40°W 38.3' U.S.G.S. Mon.
 - 1981 (Survey-Liber 4 of Surveys, Pages 499&500) Charles S. Getz, P.S. 25843-Fd. Mon. Box N30°W 37.26' P.P.; S30°W 38.25' R/W Monument; N80°W 107.93' W. End of Culvert

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 7
SW Corner Section 18 T12N-R12E
Found 12" x 5/8" iron bar with Brass Cap in Mounment Bxo
North 2619.86 feet to the W 1/4 Corner Section 18
South 2631.58 feet to the W 1/4 Corner Section 19
Accepted as best evidence

APPROVED PEER BOARD MEETING
July 20, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Found 12"x5/8" reinforcing rod with Standard Brass Cap in Monument Box
N60°E, 23.23' Set 1/2" diameter reinforcing rod
S15°E, 36.31' T.C. Re-mon. tag in Southwest face of 14" Double Trunk Cottonwood
S40°W, 38.60' Chiseled "+" in Top center of triangular concrete project marker
N25°W, 37.20' T.C. Re-mon. tag above Scott Engineering tag in Southwest face of Power Pole

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date June 30, 1999

