

SURVEY & REMONUMENTATION

SEP 17 1999

LIBER

2 PAGE 310

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 AUG -2 AM 9:10

LIBER NO. 2 PAGE NO. 310

MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

| | | |
|------------------------------------|-----------------------------|---------------|
| <u>SANILAC</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>12</u> N R <u>12</u> E | <u>A-8</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Millettics, in a field survey on April 1, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Set qr. Sec. post- Elm S62W 27; Elm 7 N17W 7
- 1981 (Survey-Liber 4 of Surveys, pages 499&500, Sanilac Co.) Charles S. Getz, P.S. 25843 Fd 1/2" Iron in bottom of Ditch-S35°E 35.90' 15" CMP; S30°E 48.31' 8" tile field; East 20.0' To 1/2" Iron bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A - 8
- W 1/4 Corner Section 19 T12N-R12E
- Found Large culvert over location of 1/4 Corner
- Reset 1/2" Iron Bar with Cap at previously recorded location
- North 2631.58 to the NW Corner Section 19
- South 2621.25 to the SW Corner Section 19
- Accepted as best evidence

APPROVED PEER BOARD MEETING
July 20, 1999

JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A - 8
- W 1/4 Corner Section 19 T12N-R12E
- 1/2" Iron Bar with Cap
- S10°E 21.50 feet to the South End of a 8' CMP
- N10°W 17.20 feet to the North End of a 8' CMP
- North 33.00 feet to a Concrete Monu Record in File No. 52 Tuscols Co. Records
- S35°E 35.90 feet to the West End of a 15" CMP
- East 55.00 feet to the East End of a 15" CMP
- N10°E 37.60 feet to a Stop Sign

Signed by John A. Millettics
Surveyor's Michigan License No. 25859

Date June 30, 1999

