

**SURVEY & REMONUMENTATION**

SEP 17 1999

LIBER 2 PAGE 313

RECEIVED FOR RECORD

99 AUG -2 AM 9:10

**SECTION**

1999 REMONUMENTATION PROGRAM  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 313  
 MICHELE VANNORMAN  
 REGISTER OF DEEDS  
 SANILAC CO., MICHIGAN

For corners in

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12</u> N R <u>12</u> E	<u>A-11</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, John A. Millettics, in a field survey on April 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Set post corner Secs. 25&36-Hemlock 10 S71½W 9½; Beech 9 N10½W 12
  - 1978 (Survey, Liber 491, page 986, Tuscola Co.) David T. Rowe, P.S. 11192-Set 3/4" pipe w/cap 11192-N55°W 66.10' RLS 11192 tag in PP: N65°W 67.32' RLS tag 11192 in Maple; S70°W 57.91' RLS tag 11192 in TP; East 18.25' RLS tag in TP
  - 1978 (Land Corner Recordation Certificate) David T. Rowe, P.S. 11192-Set 3/4" Pipe w/cap RLS 11192 at intersection of lines between East ½ Cor's. Secs. 25&36, T12N-R11E and Survey lines of R.F. Black-Accessories same as above Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 11  
 SW Corner Section 30 T12N-R12E  
 Found Standard Concrete Monument with Brass Cap  
 South 2627.90 feet to the W 1/4 Corner Section 31  
 North 2631.00 feet to the W 1/4 Corner Section 31  
 Accepted as best evidence

APPROVED PEER BOARD MEETING  
 July 20, 1999



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Standard Concrete Monument with 2" Brass Cap  
 East, 18.10' T.C. Re-mon. tag above 11192 tag in South face of Telephone pole  
 S55°W, 41.05' Northeast face of Road name sign post  
 S75°W, 58.00' T.C. Re-mon. tag above 11192 tag in Northwest face of Telephone Pole  
 N45°W, 66.12' T.C. Re-mon. tag above 11192 tag in Southwest face of Power pole  
 West, 6'+/- Centerline of Gravel

Signed by John A. Millettics  
 Surveyor's Michigan License No. 25859

Date June 30, 1999

