

SURVEY & REMONUMENTATION

SEP 17 1999

LIBER

2 PAGE 315

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM 99 AUG -2 AM 9:10
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1990

BOOK NO. 2 PAGE NO. 315
MICHELE VANNORMAN
 REGISTER OF DEEDS
 SANILAC CO., MICHIGAN

SECTION

For corners in

SANILAC

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--|-------------|
| 1. Public Land Survey | T <u>12</u> N R <u>12</u> E | <u>A-13</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John A. Millettics, in a field survey on April 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Set temporary Township corner at 80.00 chains Township corner established at 79,21 chains-Hemlock 15 North 7; Hemlock 28 S29W 8½; W. Ash 20 N6E 29; Hemlock 28 S29W 8½; Birch 17 S29W 41; Hemlock 28 S29W 21½
 - 1882 (County Surveyor's Record) John A. Teskey, Tuscola County Surveyor-Established proportionat distance from identified corners and sight trees-Stake S45W 70 links; Stake N45W 70 links
 - 1963 (Michigan State Highway Department witness card) Donald C. Pyle, P.S. 3165-Found 1" pipe buried 2' deep-S22°E 62.42' 29" Elm; N20°E 90.15' 26" Tw Elm; North 90.39' 27" Tw Elm
 - 1987 (Survey-Liber 578 pages 58 & 59) Kenneth D. Dunton, P.S. 23503-Found 1" pipe in Mon. box North 1.0' center line of M-46; S20°W 56.3' S end of curb; S45°W 48.9' W ind of curb

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 13
 SW Corner Section 31 T12N-R12E
 Found 5/8" x 12" rebar with Brass Cap in Monument Box
 North 2623.34 feet to the W 1/4 Corner Section 31
 South 2594.76 feet to the W 1/4 Corner Section 6
 Accepted as best evidence

APPROVED PEER BOARD MEETING
 July 20, 1999

jm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 5/8" diameter by 12" long reinforcing rod with Standard 2" Brass cap inside Monument Box (Monument placed August 20, 1994)
 N50°E, 46.29' set ½" diameter reinforcing rod
 S40°E, 48.28' set ½" diameter reinforcing rod 1 ft. behind back of curb
 S50°W, 45.70' set ½" diameter reinforcing rod 1 ft. behind back of curb
 N40°W, 44.63' set ½" diameter reinforcing rod



Signed by *John A. Millettics*
 Surveyor's Michigan License No. 25859

Date June 30, 1999