

JAN 19 2000

SECTION

LIBER

2 PAGE 370

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 NOV 30 PM 1:16

For corners in

Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T12N R12E	B-7
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

LIBER NO. 2 PAGE NO. 370  
MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on Nov 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- B - 7
- GLO Notes Set 1/4 Post - B. Ash 10 N3E 21, Tamarack 9 S1W 10
- OLD SURVEY LIBER - Page 410, Aug 1909 Thomas Nicol
- L.C.R.C. - Liber 1 Page 357
- Act 132 - Liber 4 Page 793
- Unrecorded survey Dated 5-12-1993 Milletics

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B - 7
- S 1/4 Corner Section 18 T12N-R12E
- Found 3/4" Iron Bar in Monu. Box
- East 2608.20 feet to the SE Corner Section 18
- West 2309.56 feet to the SW Corner Section 18
- Accepted as best evidence



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B - 7
- S 1/4 Corner Section 18 T12N-R12E
- 3/4" Iron Bar in Monu Box
- East 2608.20 feet to the SE Corner Section 18
- West 2309.56 feet to the SW Corner Section 18
- N45°E 81.93 feet to a nail in a Power Pole
- S30°E 37.15 feet to a nail in a 15" Poplar
- S45°W 59.75 feet to a nail in a 12" Poplar
- S40°W 55.25 feet to a nail in a 18" Poplar

APPROVED PEER BOARD MEETING  
NOV 19, 1999.

*gm*

Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date Nov 11, 1999