

JAN 19 2000

LIBER 2 PAGE 333

RECEIVED FOR RECORD

99 NOV 30 AM 9:03

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 333
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12</u> N R <u>14</u> E	A-3
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-3 Elm 9 S75W 13; Pine 16 N5W 18
Old Survey Liber - None
L.C.R.C. - None
Unrecorded survey - Sanilac Land dated April 1982, Milletics Dated June 1984
Act 132 - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3
SW Corner Section 6, T12N-R14E
Found 1/2" Iron bar in gravel Road Bed
North 2640.70 feet to the W 1/4 Corner
South 2687.40 feet to the W 1/4 Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

M

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 3
SW Corner section 6 T12N-R14E
1/2" iron bar in gravel road bed
North 2640.70 feet to the W 1/4 Corner
South 2687.40 feet to the W 1/4 Corner
West 10.85 feet to the North leg of a Road Sign
N35°W 38.69 feet to a nail in a Power Pole
N45°E 45.77 feet to a nail in a Power Pole
S50°E 47.55 feet to the South end of a 15" CMP

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date 11-15-99

