

JAN 19 2000

LIBER

2 PAGE 336

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:03

For corners in

LIBER NO. 2 PAGE NO. 336
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

SANILAC (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>12</u> N R <u>14</u> E	A-6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-6 Pine 12 N45W 2; B. Ash 10 S24W 27
Old Survey Liber - None
Act 132 - Liber 3 Page 528
Unrecorded Surveys - None
L.C.R.C. - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


A-6
W 1/4 Corner Section 18, T12N-R14E
Found 1/2" Iron Bar in Gravel Road Bed
North 2708.97 feet to the NW Corner of Section
South 2635.22 feet to the SW Corner of Section
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 6
W 1/4 Corner Section 18 T12N-R14E
1/2" Iron Bar in gravel road bed with cap
North 2708.97 feet to the NW Corner
South 2635.22 feet to the SW Corner
West 21.02 feet to a nail in a fence post
S60°E 40.03 feet to a nail in a Power Pole
West 33.00 feet to a 1/2" Iron bar #6504



Signed by *John A. Milletics*
Surveyor's Michigan License No. 25859

Date 11-15-99