

JAN 19 2000

LIBER 2 PAGE 338

RECEIVED FOR RECORD

99 NOV 30 AM 9:03

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 338
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

For corners in

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T 12NR 14E	A-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-8 Pine 8 S28 1/2W 19; DO 5 N25W 15 1/2
 Old Survey Linber - None
 Act 132 - Liber 4 Page 235
 L.C.R.C. - None
 Unrecorded Survey - Milletics dated Sept 1982, Nov 1990, July 1996


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8
 W 1/4 Corner Section 19, T12N-R14E
 Found 1/2" Iron Bar in gravel road bed
 North 2652.20 feet to the NW Corner
 South 2652.48 feet to the SW Corner
 Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 8
 W 1/4 Corner Section 19 T12N-R14E
 1/2" Iron Bar in gravel Road Bed
 North 2652.20 feet to the NW Corner
 South 2652.48 feet to the SW Corner
 N75°W 33.12 feet to a nail in a Tele Pole
 N45°E 44.00 feet to a nail i a Power Pole
 N40°E 44.55 feet to a 1/2" Iron
 West 32.08 feet to a nail in a Birch



Signed by John A. Milletics
 Surveyor's Michigan License No. 25859

Date 11-15-1999