

JAN 19 2000

LIBER 2 PAGE 339

RECEIVED FOR RECORD  
99 NOV 30 AM 9:03

SECTION

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 339  
MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

| <u>SANILAC</u><br>(County)            | Located In:       | Corner Code # |
|---------------------------------------|-------------------|---------------|
| 1. Public Land Survey                 | T 12N R 14E       | A-9           |
|                                       | T ___ R ___       | _____         |
|                                       | T ___ R ___       | _____         |
|                                       | T ___ R ___       | _____         |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___ | _____         |
|                                       | S ___ T ___ R ___ | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___ | _____         |
|                                       | S ___ T ___ R ___ | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- A-9 B. Ash 8 N38W 28; DO 10 S52 1/2W 4  
Old Survey Liber - None  
Act 132 - Liber 4 Page 235  
Unrecorded Survey - Milletics Dated Nov 1990  
L.C.R.C. - Liber 1 Page 328

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-9  
SW Corner Section 19, T12N-R14E  
Found 5/8" Iron Bar in gravel Road Bed  
North 2652.48 feet to the W 1/4 Corner  
South 2649.74 feet to the W 1/4 Corner  
Accepted as best evidence

APPROVED PEER BOARD MEETING  
NOV 19, 1999  
*gm*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A - 9  
SW Corner Section 19 T12N-R14E  
5/8" Iron Bar in Gravel Road Bed  
North 2652.48 feet to the W 1/4 Corner  
South 2649.74 feet to the W 1/4 Corner  
S50°W 61.80 feet to the NE Corner of a Large Rock  
S60°W 39.80 feet to the North Leg of a Road Sign  
N30°E 67.30 feet to a nail in a Power Pole  
N50°E 38.20 feet to a stop sign  
S45°E 43.35 feet to the NW Corner of a Bell Riser Box

Signed by *John A. Milletics*  
Surveyor's Michigan License No. 25859

Date 11-15-1999