

JAN 19 2000

LIBER

2 PAGE 341

RECEIVED FOR RECORD

99 NOV 30 AM 9:03

LIBER NO. 2 PAGE NO. 341
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12</u> N R <u>14</u> E	A-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-11 Birch 16 N24 1/2W 65; Elm 36 S40W 49
Old Survey Liber - None
L.C.R.C. - Liber 1 Page 328
Act 132 - Liber 4 Page 162
Unrecorded Survey Milletics Dated Sept 1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 SW Corner Section 30, T12N-R14E
Found 1/2" Iron Bar in Gravel Road Bed
North 2653.20 feet to the W 1/4 Corner
South 2658.44 feet to the W 1/4 Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 11
SW Corner Section 30 T12N-R14E
1/2" Iron Bar in gravel Road Bed with cap
North 2653.20 feet to the W 1/4 Corner
South 2658.44 feet to the W 1/4 Corner
S45°W 36.40 feet to a Stop Sign
N45°W 48.85 feet to the center of a U.S.G.S. Marker
N45°E 45.00 feet to a Stop Sign
N50°E 86.57 feet to a nail in a Power Pole

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date 11-15-1999