

SURVEY & REMONUMENTATION

SEP 20 2000

LIBER 3 PAGE 1

**2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

00 JUN 13 AM 11:56

LIBER NO. 3 PAGE NO. 1
MICHELE VANORMAN
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

For corners in **SECTION**

Sanilac

(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|----------------------------|-------|
| 1. Public Land Survey | T <u>12</u> NR <u>14</u> E | B - 7 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on March 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7	19	20	21	22	23	24						
8												
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes

- Hemlock 12" S22°E 10 Links
- Beech 9" N27°E 29 Links
- OLD Survey Liber - F.F. ROGERS 1901
- LCRC - None

Act 132 - Irvin Chope Liber 1 Page 56, Irvin Chope Liber 3 Page 178
Milletics Liber 4 Page 618

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B - 7

- S 1/4 Corner Section 18 T12N-R14E
- Found 1/2" Iron Bar in Monu. Box in Paved Surface
- West 2181.98 feet to the SW Corner Section 18
- East 2640.00 feet to the SE Corner Section 18
- Accepted as best evidence

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B - 7

- S 1/4 Corner Section 18 T12N-R14E
- 1/2" Iron Bar with cap in Monu Box
- West 2181.98 feet to the SW Corner Section 18
- East 2640.00 feet to the SE Corner Section 18
- S05°W 48.20 feet to the East end of a 24" CMP
- North 56.10 feet to the North end of a 42" CMP
- N45°W 71.00 feet to the West end of a 24" CMP
- S45°W 75.00 feet to the West end of a 24" CMP

APPROVED PEER BOARD
MEETING JUNE 12, 2000

JM

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date April 11, 2000