

SURVEY &
REMONUMENTATION

SEP 20 2000

LIBER 3 PAGE 2

RECEIVED FOR RECORD

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 13 AM 11:56

SECTION

For corners in

LIBER NO. 3 PAGE NO. 2
MICHELE VANORMAN
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T12N R14E	C - 7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on March 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C - 7 GLO Notes
Hemlock 9" S52°E 5 Links
Hemlock 9" N26E 5 Links
OLD Survey Liber - F.F. ROGERS 1901 - THOMAS NICHOL May 1902
Act 132 - Irvin Choep Liber 1 Page 56, - Irvin Choep Liber 3 Page 178
Milletics Liber 4 Page 618
LCRC None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C - 7
SE Corner Section 18 T12N-R14E
Found 1/2" Iron bar in Moun Box 3'± North of Centerline of pavement
West 2640.00 feet to the S 1/4 Corner Section 18
East 2692.40 feet to the S 1/4 Corner Section 17
Accepted as best evidence

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C - 7
SE Corner Section 18 T12N-R14E
1/2" Iron in Monu Box with cap Box being 3'± North of Center line of pavement
S45°E 79.00 feet to a nail in a Power Pole
S20°E 41.80 feet to a Stop Sign
S20°W 61.70 feet to a nail in a Power Pole
N45°W 59.10 feet to the SE Corner of a Bell Riser Box
N30°W 36.50 feet to a Stop Sign
East 2692.40 feet to the S 1/4 Corner Section 17
West 2640.00 feet to the S 1/4 Corner Section 18

APPROVED PEER BOARD
MEETING JUNE 12, 2000



Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date April 11, 2000