

SURVEY & REMONUMENTATION

APR 14 1998

SECTION REMONUMENTATION

LIBER 2 PAGE 177

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 DEC -2 AM 9:10

LIBER NO. 2 PAGE NO. 177 ESTHER LEE REGISTER OF DEEDS SANILAC CO., MICHIGAN

For corners in CUSTER TOWNSHIP

Table with columns: Sanilac (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

SURVEY & REMONUMENTATION

JAN 08 1998

SECTION Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat Private Claims

I, John A Milletics, in a field survey on July 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column E and row 2.

A. Description of original monument and accessories and/or subsequent restoration:

E - 2 GLO Notes Set 1/4 Section Post Hemlock 10 N72°E 26 Birch 6 N84°W 9 Old Survey Liber, survey dated Oct 1910 by Nicol Act 74 None Act 132 Liber 4 Page 282

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E - 2 Found Monu Box with 5/8" Iron Bar

APPROVED PEER BOARD MEETING NOV. 26, 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 2 E 1/4 Corner Section 5 T12N-R14E Custer Twp. Moun Box in place with 5/8 Iron Bar West 50.58 feet to a nail in a Fence Post N80°E 35.60 feet to top center of a culvert N85°E 44.50 feet to a telephone underground cable sign S20°E 49.15 feet to a nail in a mailbox post South 2639.92 feet to the SE Corner Section 5 North 2910.40 feet to the NE Corner Section 5



Signed by [Signature] Surveyor's Michigan License No. 25859

Date Nov 12, 1997